



Chappell Central, Inc.

1950 Trott Ave SW PO Box 916 Willmar, MN 56201 320-235-2151
Fax: Commercial/Residential 320-235-8992 Manufacturing/Shop 320-235-8995 Office 320-235-5874

December 13, 2021

Quote # 15756-4/16612

City Of Appleton
323 Schlieman Ave West
Appleton, Mn 56208

Dear EMMA:

This proposal is in regard to the replacement of Unit #4 for the police department area at the CITY OF APPLETON. The following is a breakdown of the materials we are offering for your consideration for an HVAC system.

EQUIPMENT

(unit #4)GeoComfort Element series Packaged water to air heat pumps, Model GVT048A00LTCSS, ECM direct drive blower motor, 2 stage compressor, 1 labor 5 year parts and compressor warranty, 208230V 1PH, 50amp max fuse needed, 361lbs, 41"tall x 27-3/4"wide x 25"deep

This unit comes installed with these items listed below for \$15,962.00

Pad to set unit on
Condensate piping
P/T Ports
Water solenoid valve
Piping as needed to connect her above unit your loop field piping
Honeywell thermostat (Programmable)
Sheet metal ducting needed to install the above unit to your plenums
Electrician to disconnect and reconnect
Disposal of the old unit
Freight
Installation labor

This unit has a 5 to 6-week lead time

Also, you will need to run the hot water boiler to run hot water thru the hot water coils, since a 1/4 to a 1/3 of your loop field was shut off due having leaks in it

Thank you for the opportunity to offer this proposal.

Please contact me if I can be of additional assistance or for scheduling this installation.

Sincerely,

Paul Krueger

Note: this quote is valid for 21 days.